



Utnyttingsgrad
 %-BRA = $(3\ 024 / 8\ 403) * 100 = 36\%$

Ferdig golv 1.etg **+17,8**
 Byggjehøgd **15,8m**

Parkering


Forretning/kontor/service:	38 m ² / 20 = 1,9	= 1
Industri/verkstad:	1 082 m ² / 50 = 21,64	= 21
Lager:	1 904 m ² / 100 = 19,04	= 19
Maks SUM:		= 41

Forretning/kontor/service:	38 m ² / 30 = 1,26	= 1
Industri/verkstad:	1 082 m ² / 100 = 10,82	= 11
Lager:	1 904 m ² / 300 = 6,34	= 7
Minimum SUM:		= 19

Parkeringsplassar for forflytningshemmede: min. 10%

Maks: **36 + 5 for forflytningshemma**
Minimum: **17 + 2 for forflytningshemma**

Parkering E39 Eiendom	
Type	Antall
HC	2
P	17
SUM	19



Nordhordland Næringspark

Gnr. 212, bnr. 134, Lindås kommune
 Torvhusmyrane 8
 5913 EIKANGERVÅG

Oppdragsgiver
ATR Eiendom



HELGESEN TEKNISKE BYGG AS
 5281 Valestrandfossen
 T: 56 19 34 00 www.htb.no

Prosjektnr. 2621	Dato 22.12.2017	Fase SØKNAD
----------------------------	---------------------------	-----------------------

Utomhusplan E39 Eiendom AS

Tegningsnummer A-102	Målestokk 1 : 500 / A3	Tegn. DK
--------------------------------	----------------------------------	--------------------