

5. Roof:

- 5.1. OSB 18mm;
- 5.2. 28x45mm lathing impregnated;
- 5.3. diffusion film;
- 5.4. rafters 45x195mm c/c 600mm;
- 5.5. 200mm insulation (Rockwool) above living rooms;
- 5.6. 0,20mm PE film;
- 5.7. ceiling 16mm boards- not painted;
- 5.8. ceiling of terrace and overhangs 19mm boards- surface not planed painted one time- Remmers HK Lasur Farblos colour;
- 5.9. Roofing- bitume tiles.
- 5.10. Rain water drainage system.

6. Windows:

- 6.1. Scandinavian type, painted in white colour, paint water based, with borders and reveals, inside borders- planed, outside borders not planed, 20mm;
- 6.2. all boarders painted in white colour with water based paint;
- 6.3. windows with removable sections on glasses.

7. Doors:

- 7.1. Inside and outside doors, painted in white colour, paint- water based, with borders and reveals, inside borders- planed, outside borders- not planed 20mm;
- 7.2. All borders painted in white colour with water based paint;
- 7.3. Outside doors with glass, with removable sections on glasses;
- 7.4. Inside doors without step/sill, without glass.

8. Montage elements- screws, angles sealings.

Best regards Sandefjord, 27.06.2012

