



TEL: 909 67 810

Beskrivelse

Bruvoll Camping

All wood- pine or spruce.

All panels, plinths and other details- standard producer's profiles and dimensions.

1. Outside walls:

- 1.1. outside horizontal panel 19mm boards, surface not planed painted one time- Remmers HK Lasur Farblos colour;
- 1.2. 20x45mm lathing impregnated;
- 1.3. OSB 12mm;
- 1.4. 45x95mm frame;
- 1.5. 100mm insulation (Rockwool);
- 1.6. 0,20mm PE film;
- 1.7. inside panel 16mm boards, surface planed not painted;
- 1.8. Bathroom wall- plate Durelis 12mm.

2. Inner walls:

- 2.1. inside panel 16mm boards, surface planed not painted;
- 2.2. 45x70mm frame;
- 2.3. 75mm insulation (Rockwool);
- 2.4. Bathroom wall- plate Durelis 12mm.

3. Floor:

- | | | |
|-------------------------------------|------|---|
| | 3.00 | Floor: |
| | 3.01 | 22 mm woodshingle plates |
| | 3.02 | 0,2 mm PE film |
| 3.1. Floor panels are not included. | 3.03 | Beams 48 x 148 mm c/c 60 cm |
| | 3.04 | 150 mm mineral wool insulation |
| | 3.05 | 15 x 98 mm boards under beams to support OBS plates |
| 4. Terrace: | 3.06 | OBS 12mm |

4. Terrace:

- 4.1. 45x95mm floor beams, impregnated;
- 4.2. terrace panel (larch) 26mm;
- 4.3. fence (made from simple boards 20x90mm) in pine.